

Installation Instructions

SCR Module Replacement for E1h-E4h Drives

Description

E1h–E4h drives include 3 SCR modules. This SCR module replacement kit contains all components required to install 1 replacement SCR module.

Kit Part Numbers

This installation instruction describes replacement procedures for the following spare part kits.

| Part number | Kit description | |
|-------------|--------------------------------------|--|
| 176F6647 | SCR module for 380–500 V (T5) drives | |
| 176F6648 | SCR module for 525-690 V (T7) drives | |

Table 1.1 Part Numbers for SCR Module Replacement Kits

Items Supplied

The SCR/diode module replacement kit for E1h–E4h enclosure sizes contains the following:

- 1 SCR module
- Fasteners
- 3 cc syringe of thermal grease

Safety Instructions

Only qualified, Danfoss authorized personnel are allowed to install the parts described in these installation instructions. Disassembly and reassembly of the drive must be done in accordance with the corresponding *service manual*.

AWARNING

ELECTRICAL SHOCK HAZARD

VLT® series drives contain dangerous voltages when connected to mains voltage. Improper installation, and installing or servicing with power connected, can cause death, serious injury, or equipment failure.

To avoid death, serious injury, or equipment failure:

- Only use qualified electricians for the installation.
- Disconnect the drive from all power sources before installation or service.
- Treat the drive as live whenever the mains voltage is connected.
- Follow the guidelines in these instructions and local electrical safety codes.

AWARNING

DISCHARGE TIME

The drive contains DC-link capacitors, which can remain charged even when the drive is not powered. High voltage can be present even when the warning LED indicator lights are off. Failure to wait 40 minutes after power has been removed before performing service or repair work can result in death or serious injury.

- Stop the motor.
- Disconnect AC mains and remote DC-link power supplies, including battery back-ups, UPS, and DClink connections to other drives.
- Disconnect or lock PM motor.
- Wait 40 minutes for capacitors to discharge fully.
- Before performing any service or repair work, use an appropriate voltage measuring device to make sure that the capacitors are fully discharged.

NOTICE

THERMAL BOND

- A proper thermal interface is required between the SCR/diode module and heat sink. Failure to follow these instructions results in a poor thermal bond.
- Ensure that the environment is free of airborne dust and contaminants while applying the thermal grease

Installing the SCR/Diode Module

NOTICE


FASTENER SIZE

For some spare part kits, 2 different sizes of mounting screws are included. Use the screw size that fits the heat sink.

Refer to the product *service manual* for SCR/diode module disassembly procedures. To install the replacement SCR/diode module, use the following steps.



- Clean the heat sink using a cloth and solvent or alcohol solution to remove debris and remaining thermal grease.
- 2. With the syringe, apply a layer of thermal grease to the bottom of the SCR/diode module. Once the
- module is mounted, thermal grease seeps out to coat the area between the module and heat sink. Excess grease is not a problem.
- 3. Position the SCR/diode module on the heat sink by aligning the mounting holes in the module to those in the heat sink. Refer to *Illustration 1.1*.




| 1 | Heat sink | 3 | Screw (T25) |
|---|------------------|---|------------------|
| 2 | SCR/diode module | 4 | SCR input busbar |

Illustration 1.1 Mounting the SCR/Diode Module on the Heat Sink



- 4. Insert the screws (T25) and hand tighten them.
- 5. Wait 1 minute.
- 6. Following the torque tightening sequence shown in *Illustration 1.2*, slowly tighten (maximum 20 RPM) all screws to 50% of the listed torque values.
- 7. Repeat the same tightening sequence and slowly tighten (maximum 5 RPM) all screws to 100% of the torque value.
- 8. Tighten the busbar connection terminals to the torque value listed in *Illustration 1.2*.



| Part number | Mounting torque [Nm (in-lb)] | Busbar connection torque [Nm (in-lb)] | Screw tightening order |
|-------------|------------------------------|---------------------------------------|------------------------|
| 176F6647 | 5.5 (49) | 11 (97) | 1-2-3-4 |
| 176F6648 | 5.5 (49) | 11 (97) | 1-2-3-4 |

Illustration 1.2 SCR/Diode Module Torque Tightening Sequence

30BF942.10



Danfoss can accept no responsibility for possible errors in catalogues, brochures and other printed material. Danfoss reserves the right to alter its products without notice. This also applies to products already on order provided that such alterations can be made without subsequential changes being necessary in specifications already agreed. All trademarks in this material are property of the respective companies. Danfoss and the Danfoss logotype are trademarks of Danfoss A/S. All rights reserved.

Danfoss A/S Ulsnaes 1 DK-6300 Graasten vlt-drives.danfoss.com

